
ARAWHATA WETLAND DESIGN DRAWINGS


19 JULY 2023



DRAWING SCHEDULE	
SHEET NUMBER	DESCRIPTION
1	COVER SHEET AND DRAWING SCHEDULE
2	EXISTING SITE PLAN AND NATURAL WETLAND AREAS
3	CONSTRUCTION PHASE 1 PLAN
4	CONSTRUCTION PHASE 2 PLAN
5	WETLAND OUTLET ROCK WEIR PLAN
6	WETLAND OUTLET ROCK WEIR DETAILS
7	KOHITERE STREAM LOW FLOW CHANNEL/PHASE 1 INLET CHANNEL PLAN
8	KOHITERE STREAM LOW FLOW CHANNEL/PHASE 1 INLET CHANNEL DETAILS
9	KOHITERE STREAM LOW FLOW CHANNEL/PHASE 1 INLET CHANNEL CROSS-OVER SECTION
10	STREAM CHANNEL/WETLAND BUND CHANNEL CROSS-SECTIONS
11	ROAD DRAIN DIVERSION DETAIL - PLAN 1
12	ROAD DRAIN DIVERSION DETAIL - PLAN 2 (ZOOMED)
13	SEDIMENT BASIN PLAN
14	SEDIMENT BASIN DETAILS
15	SACRIFICIAL WETLAND CROSS-SECTION
16	CONTOUR BUND CROSS-SECTION
17	BIOREACTOR PLAN
18	BIOREACTOR DETAILS
19	NATURAL VS CONSTRUCTED WETLANDS AND MAINTENANCE PLAN







- Land Boundary
- Deeper cut wetland areas
- → Proposed outlet weir location
- Proposed Bund
- Existing bund to be increased in height
- Component Label Phase 1
- → Existing/new channel farm drains
- Subsurface perforated drain pipe laid in invert of existing/new drains then drain backfilled with wood chips, bark (Bioreactor)
 - Bioreactor treated flow discharge pipe (solid pipe)
- Channel taking flow from drains in vegetable growing area to feed into wetland
- Approximate edge of wetland wetted area
- Sediment Basin

Construction Phases

Phase 1

- Existing natural wetland areas
 -)(

Existing culvert to be retained

Wetland internal bund (~0.5m

Sacrificial Wetland

- Kohitere low flow channel
- Kohitere low flow channel diversion structure


New culvert, arrow indicating flow direction

Wetland maintenance access tracks (existing and proposed)

- Sodimont Basin alongside ovi

- Sediment Basin alongside existing Joblins Drain/site boundary (A see plan for location)
- Installation of perforated pipe in existing Joblins Drain channel (within the site boundary) and drains as well as new drains along the property boundary either side of Joblins Drain, backfilled with woodchips/bark/hay for groundwater treatment (Blue dashed arrows). (B)
- Construction of new channels at flatter grade than ground slope such that water can be discharged onto surface of wetlands from Kohitere stream and Joblins Drain. (purple arrows) (C)
- Surface water overflow from sediment trap directed into new channels (purple) under gravity. (D)
- Partial planting through wetland areas. (E)
- Retention of existing groundwater pump + southern well for irrigation (F)(G)
- Plants for phase 1 need to be purchased.
- Cleaning out/deepening farm drains and roadside drains such that groundwater is intercepted. Invert to still be sloped and discharged to either Arawhata Stream or the Phase 1 wetlands. (I)
- Extension of stopbanks along Arawhata Stream west side. (J)
- Sediment trap to be retained as is (M)
- Lower section of wetland perimeter bund for discharging treated flow (outlet weir) (N)
- Kohitere low flow channel/fish passage channel (partial existing location, partial new) (P)






0 200 40

Arawhata Wetland

Diagram 1: Construction Phase 1

Jacobs



Legend

- Land Boundary
- Deeper cut wetland areas
- Proposed outlet weir location
- Proposed Perimeter Bund
- Existing Bund Height to be increased
- Proposed outlet weir location
- Component Label Phase 2
- Surface irrigation perforated pipe to irrigation Kohitere stream alluvial fan
- → Existing/new channel farm drains
- Subsurface perforated drain pipe laid in invert of existing/new drains then drain backfilled with wood chips, bark (Bioreactor)
- Bioreactor treated flow discharge pipe (solid pipe)
- Channel taking flow from drains
 - in vegetable growing area to feed into wetland
- Approximate edge of permanent wetland wetted area (other than in extended dry periods)
- Sediment Basin

Construction Phases

- Phase 1
- Phase 2
- Kohitere low flow channel
- Wetland maintenance access tracks (Existing and proposed)

N 0 200 400 m

Phase 2 Components

- Construction of new channels at flatter grade than ground slope such that water can be discharged onto surface of wetlands from Whelans Drains. (C)
- More planting in Phase 1 and Phase 2 areas (E)
- New bund on east side of existing Arawhata Stream to contain Phase 2 wetland. (J)
- A lower section of bund/stopbank will be built at the downstream end alongside Hokio Beach Road to discharge treated wetland flow into the main Arawhata drain. (N)
- New groundwater collection drains along Hokio Beach road and wetland site boundary. (H)
- Installation of small new pump to irrigate sediment pond water into Kohitere Stream alluvial fan in areas where it cannot flow under gravity. (O)

Stream Naturalisation/Wetland Naturalisation Principals


- Existing bund to be used as foundation for higher bund in same location
- Bund toe to be at least 1m from the stream invert
- Avoidance of straight lines (other than existing bund)
- Planting (species TBC) to be used on wider floodplain above normal water depth





Jacobs

NZGD2000 Scale: 1:8500

Arawhata Wetland Diagram 1: Construction Phase 2










DRAWING TITLE: KOHITERE STREAM LOW FLOW CHANNEL/PHASE 1 INLET CHANNEL PLAN









LEGEND

EXISTING GROUND


PROPOSED GROUND

NORMAL FLOW DEPTH - PRIMARILY GROUNDWATER INFLOW DRIVEN


APPROX. FLOW DEPTH IN LARGER STORMS -

TO SHOW HOW FLOW WILL SPREAD OVER AREA BETWEEN BUND

PLANTING - VARIABLE SPECIES




Narrow section



SHEET NUMBER: 10


DRAWING TITLE: ARAWHATA STREAM CHANNEL/WETLAND BUND CHANNEL TYPICAL CROSS SECTIONS









DRAWING TITLE: ROAD DRAIN DIVERSION DETAIL - PLAN 1









DRAWING TITLE: JOBLINS SEDIMENT BASIN PLAN




Source: T + T










<u>DRAWING TITLE:</u> SACRIFICIAL WETLANDS CROSS-SECTION (KOHITERE AND JOBLINS)





LEGEND

----EXISTING GROUND
PROPOSED GROUND

Inflow from upstream channel



0.5m contour bunds on contour. Ends to tie into existing ground such that ponding area is created.
Bund top level to be flat such that water overtops over whole length

SHEET NUMBER: 16

DRAWING TITLE: WHELANS CONTOUR BUND CROSS-SECTION






Perforated Pipe
Solid Pipe


See Sheet 18 for details

SHEET NUMBER: 17

DRAWING TITLE: BIOREACTOR PLAN







EARTH BACKFILL DEPTH OF ABOVE THE PIPE COVER 50mm ZONE MIN DRAFT 150mm MIN, OR AS SPECIFIED PIPE OUTSIDE 1 m deep pipe zone DIAMETER OF organic media backfill LARGEST PIPE 100mm 250mm 100mm 250mm min min min 300mm Perforated 300mm Perforated 300 mm Pipe Solid Pipe Pipe **TYPICAL 3 PIPE TRENCH**



SHEET NUMBER: 18

DRAWING TITLE: BIOREACTOR DETAILS