



EARTHWORKS DEPTH RANGE			EARTHWORKS DEPTH RANGE		
LOWER	UPPER	COLOUR	LOWER	UPPER	COLOUR
-11.0	to -10.0	Red	0.0	to 1.0	Light Blue
-10.0	to -9.0	Red	1.0	to 2.0	Light Blue
-9.0	to -8.0	Red	2.0	to 3.0	Light Blue
-8.0	to -7.0	Red	3.0	to 4.0	Light Blue
-7.0	to -6.0	Red	4.0	to 5.0	Light Blue
-6.0	to -5.0	Red	5.0	to 6.0	Light Blue
-5.0	to -4.0	Red	6.0	to 7.0	Light Blue
-4.0	to -3.0	Red	7.0	to 8.0	Light Blue
-3.0	to -2.0	Red	8.0	to 9.0	Light Blue
-2.0	to -1.0	Red			
-1.0	to 0.0	Red			

NOTES:

- TOTAL CUT VOLUME 118,000m³.
- TOTAL FILL VOLUME 83,000m³.
- TOTAL EARTHWORKS AREA 114,000m².
- EARTHWORKS SHOWN IN BULK VOLUMES ONLY (NEAREST 1m).
- GOLF COURSE ROUTING AND LEVELS BY DARIUS OLIVER, PLANET GOLF.
- FINAL DESIGN LEVELS AND EARTHWORK EXTENTS TO BE DETERMINED AT THE TIME OF CONSTRUCTION.
- FINAL EROSION AND SEDIMENT CONTROL METHODS AND DESIGN TO BE DETERMINED BY CONTRACTOR AT THE TIME OF CONSTRUCTION.
- FAIRWAY AND GREENS WILL BE CONSTRUCTED IN ACCORDANCE WITH THE MAHI TAHI CONSTRUCTION PROCESS DATED 1ST DECEMBER, 2020.
- VOLUMES CALCULATED BETWEEN EXISTING SURFACE AND PROPOSED SURFACE.

LEGEND:

- CONSTRUCTION NO GO AREA
- SILT FENCE
- FIRST LINE OF VEGETATION APPROX
- 200m OFFSET TO FIRST LINE OF VEGETATION